


TOTAL PARKING IN LOT	REQUIRED MINIMUM NUMBER OF ACCESSIBLE SPACES
1 TO 25	1
26 TO 50	2
51 TO 75	3
76 TO 100	4
101 TO 150	5
151 TO 200	6
201 TO 300	7
301 TO 400	8
401 TO 500	9
501 TO 1000	2 PERCENT OF TOTAL 20 PLUS 1 FOR EACH 100 OVER 1000
1001 AND OVER	

*1 OF EVERY 8 HC STALLS MUST BE "VAN ACCESSIBLE"

TIRE STOPS(OPTIONAL)

END ISLANDS ARE RECOMMENDED FOR LARGER, HIGH-VOLUME LOTS. USE LANDSCAPED ISLANDS ADJACENT TO REGULAR STALLS

NOTE: 90° PARKING MAY SHARE HATCHED AREA. ANGLED PARKING REQUIRES INDEPENDENT HATCHED AREAS.



RAMP (A) SHOULD BE MOVED INTO THE SIDEWALK, PROVIDED SIDE SLOPES ARE LESS THAN 1:10 AND 5' OF LEVEL SIDEWALK IS MAINTAINED AT THE ENTRY DOOR.

MINIMIZE THE USE OF TIRE STOPS NEAR HIGH PEDESTRIAN TRAFFIC.

1. STANDARD HANDICAP PARKING SPACES ARE TO CONFORM TO SECTION 3313.2 OF THE KENTUCKY BUILDING CODE.
2. THE FIRST HANDICAPPED PARKING SPACE MUST BE DIMENSIONED AND SIGNED AS "VAN ACCESSIBLE". 1 OF EVERY 8 HC SPACES MUST BE "VAN ACCESSIBLE".
3. MINIMUM MOUNTING HEIGHT OF SIGNAGE FOR HANDICAP PARKING IS 6' FROM GROUND TO BOTTOM OF THE LOWEST SIGN.
4. SIGNS ARE TO BE CENTERED IN FRONT OF EACH SPACE ALONG WITH THE INTERNATIONAL HANDICAP SYMBOL PAINTED IN THE VEHICLE AREA IN EITHER YELLOW OR WHITE PAINT.

**REFER TO THE AMERICANS WITH DISABILITIES ACT (ADA), [ACCESSIBILITY GUIDELINES FOR BUILDINGS AND FACILITIES](#) FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

**ADA ACCESSIBILITY REQUIREMENTS ARE ENFORCED BY BUILDING INSPECTION.

PASSENGER VEHICLES (ADA)